



Republic of the Philippines
SURIGAO DEL SUR STATE UNIVERSITY
 Lianga Campus
 Lianga, Surigao del Sur
 Contact #:09206609263

Bids and Awards Committee on Goods

REQUEST FOR QUOTATION (RFQ)
“Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building”
 RFQ No: 005

1. The Surigao del Sur State University (SDSSU) - Main Campus, through **the Special Trust Fund** intends to apply the sum of *Four Hundred Ninety Five Thousand Seventy Seven Pesos & 67/100 (P 495,077.67)* being the approved Budget for the Contract (ABC) to payments for the **“Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building”** for which this Request for Quotation is issued.
2. The SDSSU, herein after referred to as “the Purchaser” now request you to submit price quotation for the supply and delivery of the following:

Item No.	Description		Qty.	Unit
	Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building			
1	Hardware	1 lot		
	Nylon # 16	1 lot	3	rolls
	Deformed Steel Bars, 16 mm Ø x 6.0 m grade 40		28	length
	Deformed Steel Bars, 12 mm Ø x 6.0 m, grade 40		28	length
	Deformed Steel Bars, 10 mm Ø x 6.0 m, grade 40		68	length
	Tie Wire G.I. , #16		7	kilos
	Hacksaw Blade		8	pcs.
	CWN Nails 3		37	kgs.
	CW Nails #1-1/2"		30	kgs.
	CW Nails 2-1/2"		50	kgs.
	CW Nails 4"		100	kgs.
	CW Nails 1"		10	kgs.
	machine bolts nut & double washers 5/8"Ø x 8"		336	bd.ft.
	post strap 1/4"x2" x 16"			pcs.

			24	
	Coal tar		25	gals
	Long span metaplas roof 2.0 mm thk, rib type, color blue		244	ln.m
	Metaplas ridge roll 2.0 mm thk		15	pcs
	Metaplas end wall flashing 2.0 mm thk		22	pcs
	Roof Sealant		4	qrtz
	Tekscrew 2-1/2"		400	pcs
	Blind Rivets 1/8		1	box
	Plywood Ordinary , 1/2" x 4' x 8'		12	pcs
	Portland Cement Type 1, (40 kgs)		22	Bags
2	Lumber	1 lot		
	Lauan or Equivalent, 50 - 2" x 2" x 12'		280	bd.ft
	Coco lumber or Equivalent, 350 pcs 2" x 2" x 12'		1,400	bd.ft.
	Coco lumber or Equivalent, 200 pcs 2" x 3" x 12'		1,200	bd.ft.
	Lawaan or Equivalent, purlins , 76 - 2"x4"x12'		608	bd.ft.
	Yakal , bottom chord , 26 - 2"x5"x16'		340	bd.ft.
	Yakal , splice block, 7 - 2"x5"x16'		93	bd.ft.
	Yakal , king post , 3.5 - 2"x5"x16'		47	bd.ft.
	Yakal , wood block , 14 - 2"x5"x16'		180	bd.ft.
	Yakal , top chord , 20 - 2"x6"x16'		312	bd.ft.
	Yakal , collar plate , 1.5 - 2"x6"x16'		24	bd.ft.
	Yakal , vertical & diagonal , 47 - 2"x4"x8'		248	bd.ft.
	Yakal , cross bracing , 4 - 2"x4"x16'		43	bd.ft.
	Yakal , facia boards , 11 - 1"x12"x16'		176	bd.ft.
3	Sand and Gravel			
	Screened Gravel 3/4"	I lot	3	cu.m.
	Washed Sand		2	cu.m.

4	Project Sign Board			
	Project Sign Board		1	unit
5	Labor	1 lot	1	lot

3. A set of technical specifications for the above items are provided in Attachment 1. All items listed under the purchasers specifications must be complied on a pass-fail basis. Failure to meet any one of the requirements will result to rejection.
4. Bidding procedures will be conducted in accordance with the provisions of the Implementing Rules and Regulations-A (IRR-A) of Republic Act 9184.
5. It is the intent of the Purchaser to evaluate the quotation for each item separately, and award will be made to the quotation or combination of quotations resulting in the overall lowest cost. Quotation for one or more or all items will be considered. Contract Award will be made to the lowest evaluated quotation (s) meeting purchaser's technical specifications.
6. Quotations must be delivered at the BAC Office of Surigao del Sur State University, Lianga Campus, Lianga, Surigao del Sur not later than 10:00 AM of November 25, 2015.
7. Your prices must be quoted in Philippine Peso and must include the unit price and total price, inclusive of all taxes to be paid and other incidental cost to the delivery site if the contract is awarded.
8. All quotations must be typewritten and must be placed in sealed envelope marked **“Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building (RFQ No. 005).”**
9. Quotations shall be valid for sixty (60) calendar days from the Opening of Bids.
10. The delivery period shall be within fifteen (15) calendar days from receipt of the Notice to Proceed (NTP).
11. DELIVERY SITE: Surigao del Sur State University (SDSSU) Lianga Campus, Lianga Surigao del Sur.
12. The applicable rate for late deliveries is one tenth (1/10) of one percent (1%) of the cost of the unperformed portion for every day of delay. The maximum deduction shall be ten percent (10%) of the amount of contract. Once the cumulative amount of liquidated damages reaches ten percent (10%) of the amount of the contract, the procuring entity shall rescind the contract, without prejudice to other courses of action and remedies open to it.
13. The SDSSU reserves the right to accept or reject any quotation, and to annul the bidding process and reject all quotations at any time prior to Contract award, without thereby incurring any liability to the affected bidder or bidders and to waive any minor defects or infirmities therein and to accept such quotation as may be considered advantageous to the government.
14. The prospective bidder shall submit the following:
 - a. Quotation Form
 - b. Technical Specification
 - c. Certificate of PHIL-GEPS Registration

Sgd. CYNTHIA P. SAJOT, Ph. D.
Campus Director



Republic of the Philippines
SURIGAO DEL SUR STATE UNIVERSITY
 Lianga Campus
 Lianga, Surigao del Sur
 Contact #:09206609263

QUOTATION FORM

Date: _____
 RFQ No. 005

The Chairman
 The Bids and Award Committee on Goods
 SDSSU-Lianga Campus

- 1) Having examined the subject Request for Quotation including the Technical Specifications, we, the undersigned offer to supply and deliver the following items (with our unit price and total)

Item No.	Description		Qty.	Unit	Unit Price	Total
	Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building					
1	Hardware	1 lot				
	Nylon # 16	1 lot	3	rolls		
	Deformed Steel Bars, 16 mm Ø x 6.0 m grade 40		28	length		
	Deformed Steel Bars, 12 mm Ø x 6.0 m, grade 40		28	length		
	Deformed Steel Bars, 10 mm Ø x 6.0 m, grade 40		68	length		
	Tie Wire G.I. , #16		7	kilos		
	Hacksaw Blade		8	pcs.		
	CWN Nails 3		37	kgs.		
	CW Nails #1-1/2"		30	kgs.		
	CW Nails 2-1/2"		50	kgs.		
	CW Nails 4"		100	kgs.		
	CW Nails 1"		10	kgs.		
	machine bolts nut & double washers 5/8"Ø x 8"		336	bd.ft.		
	post strap 1/4"x2" x 16"		24	pcs.		
	Coal tar		25	gals		

	Long span metaplas roof 2.0 mm thk, rib type, color blue		244	ln.m		
	Metaplas ridge roll 2.0 mm thk		15	pcs		
	Metaplas end wall flashing 2.0 mm thk		22	pcs		
	Roof Sealant		4	qrtz		
	Tekscrew 2-1/2"		400	pcs		
	Blind Rivets 1/8		1	box		
	Plywood Ordinary , 1/2" x 4' x 8'		12	pcs		
	Portland Cement Type 1, (40 kgs)		22	Bags		
2	Lumber	1 lot				
	Lauan or Equivalent, 50 - 2" x 2" x 12'		280	bd.ft		
	Coco lumber or Equivalent, 350 pcs 2" x 2" x 12'		1,400	bd.ft.		
	Coco lumber or Equivalent, 200 pcs 2" x 3" x 12'		1,200	bd.ft.		
	Lawaan or Equivalent, purlins , 76 - 2"x4"x12'		608	bd.ft.		
	Yakal , bottom chord , 26 - 2"x5"x16'		340	bd.ft.		
	Yakal , splice block, 7 - 2"x5"x16'		93	bd.ft.		
	Yakal , king post , 3.5 - 2"x5"x16'		47	bd.ft.		
	Yakal , wood block , 14 - 2"x5"x16'		180	bd.ft.		
	Yakal , top chord , 20 - 2"x6"x16'		312	bd.ft.		
	Yakal , collar plate , 1.5 - 2"x6"x16'		24	bd.ft.		
	Yakal , vertical & diagonal , 47 - 2"x4"x8'		248	bd.ft.		
	Yakal , cross bracing , 4 - 2"x4"x16'		43	bd.ft.		
	Yakal , facia boards , 11 - 1"x12"x16'		176	bd.ft.		
3	Sand and Gravel					
	Screened Gravel 3/4"	1 lot	3	cu.m.		
	Washed Sand		2	cu.m.		
4	Project Sign Board					
	Project Sign Board		1	unit		

5	Labor	1 lot	1	lot		

- 2) We undertake, if our Quotation or Bid is accepted, to deliver the above goods within the *fifteen (15)* days delivery period.
- 3) We agree to abide by this Quotation/Bid for a period of *sixty (60) days* after the dated deadline of submission specified in your RFQ.
- 4) We understand that payment for items delivered will be made to the winning supplier within thirty (30) days after inspection and acceptance of goods delivered.

Company Name: _____

Address: _____

Signature Over Printed Name: _____



Republic of the Philippines
SURIGAO DEL SUR STATE UNIVERSITY
Lianga Campus
Lianga, Surigao del Sur
Contact #:09206609263

TECHNICAL SPECIFICATIONS

Purchaser's Specifications	Supplier's Specifications (please state "Comply" or "Not Comply")
Supply and Delivery of Materials for Construction of Roof for Two (2) Storey HRM Building	
Hardware	
Nylon # 16	
Deformed Steel Bars, 16 mm Ø x 6.0 m grade 40	
Deformed Steel Bars, 12 mm Ø x 6.0 m, grade 40	
Deformed Steel Bars, 10 mm Ø x 6.0 m, grade 40	
Tie Wire G.I. , #16	
Hacksaw Blade	
CWN Nails 3	
CW Nails #1-1/2"	
CW Nails 2-1/2"	
CW Nails 4"	
CW Nails 1"	
machine bolts nut & double washers 5/8"Ø x 8"	
post strap 1/4"x2" x 16"	
Coal tar	
Long span metaplas roof 2.0 mm thk, rib type, color blue	
Metaplas ridge roll 2.0 mm thk	
Metaplas end wall flashing 2.0 mm thk	
Roof Sealant	
Tek screw 2-1/2"	
Blind Rivets 1/8	
Plywood Ordinary , 1/2" x 4' x 8'	
Portland Cement Type 1, (40 kgs)	
Lumber	
Lauan or Equivalent, 50 - 2" x 2" x 12'	
Coco lumber or Equivalent, 350 pcs 2" x 2" x 12'	
Coco lumber or Equivalent, 200 pcs 2" x 3" x 12'	
Lawaan or Equivalent, purlins , 76 - 2"x4"x12'	
Yakal , bottom chord , 26 - 2"x5"x16'	
Yakal , splice block, 7 - 2"x5"x16'	
Yakal , king post , 3.5 - 2"x5"x16'	
Yakal , wood block , 14 - 2"x5"x16'	
Yakal , top chord , 20 - 2"x6"x16'	
Yakal , collar plate , 1.5 - 2"x6"x16'	

Yakal , vertical & diagonal , 47 - 2"x4"x8'	
Yakal , cross bracing , 4 - 2"x4"x16'	
Yakal , facia boards , 11 - 1"x12"x16'	
Sand and Gravel	
Screened Gravel 3/4"	
Washed Sand	
Project Sign Board	
Project Sign Board	
Labor	
Labor	